Insurance Damage Estimate

Version: 1.0 Generated: 2025-08-18T10:00:00Z Currency: USD

Total Project Cost: USD 709.93

Estimate reasoning

Toilet overflow with standing contaminated water observed. Replace toilet (toilet contaminated/stained) rather than attempt reset. Perform moisture inspection to confirm affected area and depth. Apply antimicrobial treatment to estimated 25 SF of floor and adjacent substrates due to sewage/dirty-water contamination. Provide containment, debris disposal, re-caulk joints and final clean to return space to sanitary condition.

| ID | Item | Qty | Unit | Unit Price | Tax | Total | Category |
|----|--|-----|--------------|------------|--------------|----------------------------------|----------|
| | | | USD 541.5 | | USD | | |
| 1 | R&R Toilet | 1 | 3 | USD 19.65 | 561.18 | Plumbing | |
| 2 | Moisture inspection + photos | 1 | USD 35.00 | USD 0.00 | USD 35.00 | Inspection/ Documenta tion | |
| 3 | Antimicrobial treatment | 25 | USD 0.75 | USD 0.00 | USD 18.75 | Mitigation | |
| 4 | Site protection & masking (small bath) | 1 | USD 40.00 | USD 0.00 | USD 40.00 | Mitigation | |
| 5 | Debris bag & dispose (small) | 1 | USD 15.00 | USD 0.00 | USD 15.00 | Debris/Disp osal | |
| 6 | Caulk wall-to-tile joint | 10 | USD 2.00 | USD 0.00 | USD 20.00 | Finishes | |
| 7 | Final clean | 1 | USD 20.00 | USD 0.00 | USD 20.00 | Cleanup | |

Appendix: Item Details

1 — R&R; Toilet

Full remove & replace of damaged two-piece toilet due to contaminated overflow; includes new wax ring and install

Tags: toilet, replace

2 — Moisture inspection + photos

Moisture mapping and photo documentation of affected floor and adjacent walls to determine penetration and drying needs Tags: water, inspection

3 — Antimicrobial treatment

Apply antimicrobial to affected floor tile/grout and exposed substrates (estimated 25 SF small bathroom floor area) to mitigate contamination from sewage/dirty water

Tags: antimicrobial

4 — Site protection & masking (small bath)

Containment, floor protection and masking to limit dust/contamination during work

Tags: containment, dust

5 — Debris bag & dispose (small)

Bag and haul removed toilet and contaminated debris

Tags: disposal

6 — Caulk wall-to-tile joint

Re-caulk perimeter joints as needed after cleaning and disinfection (approx. 10 LF)

Tags: sealant

7 — Final clean

Final wipe-down, remove masking, sanitation after work completion

Tags: cleaning